Approximate quantities for Restoring Angadi Doddakere No. 285, Mudgere Taluk.

Particulars of work	Per	Quantity	Rate	
			In figures	In words
1. *Bund R. L.* 77·00				
Earthwork to bund including watering and tamping	C.yd.	21,906		
Providing grade stones, new	No.	20		
Do Index	..	20		
Do B. M., stones	...	2		
Do Date and Register number stone ...	..	1		
Total ...	...	...		
2. *Masonry weir R. L.* 72·50·45 long.				
Earthwork excavation chargeable to bund ...	...	...		
Surki concrete for foundation body wall and returns	C.ft.	522		
Burnt brick in surki mortar	„	1,597		
Burnt stone slabs 6" thick	S.ft.	185		
Plastering with surki mortar	S qr.	12·38		
Constructing rough stone apron with jelly backing and wedging including 3 miles lead.	C.yd.	45		
Cutting joggles in joints of slabs over body wall ...	No.	5		
Earthwork at flanks, consolidation and etc. ...	Lump	sum		
Total ...	...	...		
3. *Sluice* 67·50.				
Earthwork cutting the bund and forming for the construction of sluice chargeable to bund.	...	...		
Filling the foundation with surki concrete with stone jelly.	C.ft.	129		
Burnt brick in surki mortar	„	338		
Burnt stone slabs 6" thick	S.ft.	37		
Drilling holes in arifice slabs	No.	3		
Plastering with surki mortar	Sqr.	2		
6" cast iron pipe including carting railway frieght and fixing, etc., complete.	R.ft.	27		
Providing and fixing plug and rod with lifting arrangements, etc., complete.	Lump	sum		
Rough stone apron and wings at rear ..	Lump	sum		
Total for sluice ...	...	...		

L. A. H. WINCKLER,
Executive Engineer.

MYSORE RAILWAYS, MYSORE.

Abstract Notification dated 23rd August 1929.

Attention of the intending contractors is hereby invited to the Notice, calling for tenders for "Improvements to Railway Audit Office at Mysore", published in page 886 of Part VI of the *Mysore Gazette*, dated 22nd August 1929. Tenders will be received any day up to 2 P.M. of 2nd Septepber 1929.

Y. K. RAMACHANDRA RAU,
Executive Engineer.